

Mighty Tree Movers Inc.
PO Box 12
Los Gatos CA 95031
Phone: 408-464-5200

RECEIVED

OCT 19 2018

City of Carmel-by-the-Sea
Planning & Building Dept.



Cindy Hunter
Cindy Hunter
25974 Mission St
Carmel CA 93923

Estimate #:	0000862
Date:	August 28, 2018
Estimate Total (USD):	

To view your estimate online » Go to: <https://mightytreemovers.freshbooks.com/view/3i5QQsEwfxeHQFd2>

Item	Description	Unit Cost (\$)	Quantity	Price (\$)
Tree Box and crane	<p>MTM will box (1) Coast live oak and crane to new location about 50 feet from current location. The 4 sides will first be excavated and the box sides installed and secured with steel banding. Then the bottom of the box will be excavated and built board by board. Once complete a 75 ton crane will enter and set up in center of property to hoist into new position. Once in new receiving hole, tree will be backfilled with native soil with some composted organic and soil mixed in. Fertilizer and root growth hormones added of time of backfill. Tree will then be heavily watered in.</p> <p>Site conditions: Current site has a home and several trees that will have to be removed first. This includes large oak tree branch overhanging the driveway that would prevent crane access. Utilities must be cleared from tree location and new spot. Entire site must be made ready and flat for crane travel and access. Rain could delay job.</p> <p>The planting location is very limited. Some trimming and possibly the removal of one small redwood may be necessary.</p> <p>*This bid does not include backfilling hole where tree came from or compacting soil for engineering requirements. Water must be available on site for entire process.</p> <p>**The tree will most likely require some pre-watering before boxing process. If client can manage, all the better, if site visit(s) is/are required to water oak, additional costs may apply.</p>		1	
Arborist	ISA Certified Arborist overseeing entire project. WE-8858 CA Lic# 916423		0	
Release 1	Our tree spade and cranes used large heavy pieces of equipment that may leave ruts on turf. MTM is not responsible for any damage done to areas that have to be traveled on to complete the move. This includes asphalt and cement pathways.		0	
Green Tree Guarantee	<p>MTM will warranty the workmanship of the oak tree for 1 year after transplant. Proper irrigation must be installed and maintained for warranty to remain in effect.</p> <p>Replacement tree will be a Coast live oak with a trunk diameter of 6 to eight inches and canopy of approximately 15 feet tall. This tree will be delivered and planted in location of failed oak tree. Access is required from front of property, fencing or any</p>		1	

Irrigation	<p>obstructions will need to be removed. Warranty does not include removal of dead tree.</p> <p>Irrigation: MTM will run a timed 5/8's inch temporary drip irrigation system to relocated tree. This system will run off of local water source within 150 feet from new location with a minimum 45 PSI. Trees will receive appropriate amount of water dictated by the season.</p>	1	
	Subtotal:		
	Estimate Total (USD):		